



23/1 2017
 Kleitar 2, Vestmannvegum
LOTA
 www.lota.is : lota@lota.is
 Andrius Elisson
 tel. 120556-2749

- Uwagi:
- 1) Płyty dachowe należy mocować do blachy trapezowej wg pokazanych szczegółów i wytycznych producenta.
 - 2) Płyty ścienne należy mocować do konstrukcji stalowej wg pokazanych szczegółów i wytycznych producenta.
 - 3) Wszystkie styki łączonych płyt należy uszczelniać wg wytycznych producenta.
 - 4) Płyty dachowe i ścienne należy dotoczyć na budowie do pokazanych otworów i potacji dachu.
 - 5) Powierzchnie boczne wszystkich płyt należy zabezpieczyć obróbką blacharską wg pokazanych szczegółów.
 - 6) Mocowanie obróbek blacharskich należy wykonać za pomocą wkrętów samowierzących z podkładką uszczelniającą.
 - 7) Montaż płyt, obróbek blacharskich i uszczelnienie należy wykonać z uwzględnieniem detali architektonicznych.
- Remarks:
- 1) Roof panels should be fastened to the trapezoidal sheet as shown by the details and the manufacturer's guidelines.
 - 2) Wall panels should be fastened to the steel structure as shown by the details and the manufacturer's guidelines.
 - 3) All contacts of assembled panels should be sealed by the manufacturer's guidelines.
 - 4) Roof panels and wall should be cut on site to the shown holes and slope of the roof.
 - 5) Side surfaces of all panels should be secured by metal plating as shown details.
 - 6) Fixing the flashings must be done using self-drilling screws and sealing washer.
 - 7) Mounting panels, flashings and seals should be performed taking into account the architectural details.

Rev: A-05/2017 - zmiana porządku i detali otworów / change connections and details of flashings

INVESTOR	Yabimo sp. z o.o. Services sp.k.
PROJECT	YS/2016/789, Frystingeyman (cold storage)
OBJECT	STRUKTURA I DETALE ŁĄCZEŃ PŁYT
STADIUM	SHOP DRAWINGS
WYKONANIE	Ing. iR. AnnaLise Datta
MATERIAL	S240-3355
DATA	11/10/2016
SCALE	1:50
FORMAT	A1 (DWG, PDF)
REV.	A-05/2017